



# 2/3 V.O.C Nagar, 2nd Street, Anna Nagar East, Chennai - 600 102.

Tel: 044-4509 0323, Mob: 9840026130, 9840757732

Email: rajesh@sdrconstruction.org





Site Layout

## **Ground Floor**







**Ground Floor** 



Floor

Toilet

3'0"x4'0"

Toilet 3'0"x4'0"

Plan



## Specification

Structure : RCC frame structure with 9" brick external walls and 41/2" brick partition wall.

Design : Architect design as per vasthu.

**Plastering** 

Main door

: Ceiling, inner & outer walls plastering in cement

. Coming, arrior of outer mane placetering in o

with neat finish.

Flooring 2'x 2' Vitrified Tiles in all rooms with 4" skirting.

: Quality Teak Wood frame with Panelled door with

varnish finish and brass fittings.

Other door : Quality Country Wood frame with flush door with

enamel Paint and power coated fitting.

Window: Wood frame with glazed shutters - openable

windows with M.S. Grills.

Plumbing : Concealed CPVC Pipe Line in bathroom, PVC

: Concealed CPVC Pipe Line in bathroom, PVC pipes for rain water, sanitary waste

Sanitary : Line and under ground drainage. Bath rooms with

bore well water.

Kitchen : 20 mm Black granite counter with stainless steel

sink with drain board, will be provided.

Toilet : EWC/IWC white color sanitary ware (Parryware or

Equivalent) Washing machine point, Geyser point, One shower point, Glazed tiles upto

7' height, Wash Basins.

Painting

 Grills - Zink Chromite non-corrosive primer with enamel paint.

Electrical

: Three Phase power supply with concealed wiring of ISI Anchor Switches or Equivalent Earth leak

The electrical points as per architects drawing.

Finishes : Inter

: Internal Surface will be finished with two coat of

path with Acrylic Emulsion Paint.

Exterior Surface shall be finished wirth ACE acrylic

emulsion paint.

Staircase : Railing - MS Grill.

Rainwater : Rain water harvesting will be done.

Pest control : Pre construction anti-termite treatment.

circuit breaker.

Generator : Will be provided.

